



BIG FEATURES, NIMBLE SIZE

No Job Too Small for the Newest
Member of the DECKHAND® Family

Introducing **DECKHAND® XS**

PRECISE

360° rotation, tilt and shift functions allow
for total control and precise load placement.

SAFE

Load holding valves, proximity sensors and
auto-clamp design ensure a safe lift every time.

VERSATILE

Interchangeable arms allow operator to
easily switch between handling drill rod,
pipe, poles and other material.



LaValley Industries.

OUR TOOLS IN YOUR HANDS, GET JOBS DONE!





TACKLING BIG PROJECTS IN A PINT SIZED PACKAGE

KEY BENEFITS

360° continuous rotation, tilt, and shift functions deliver unmatched control and load placement.

Convenient in-cab display and joystick controls allow the operator to safely operate, monitor and adjust all XS functions from inside the excavator cab.

Uses DECKHAND® family of interchangeable arms to easily switch between different types and sizes of pipe, drill rod, poles and casing.

Load locking valves ensure that the load is never dropped regardless of hydraulic pressure.

Load can be securely positioned and held in a vertical orientation.

Excavator's auxiliary hydraulic circuit powers the DECKHAND even in the most adverse weather conditions.

Load can be safely lifted from an off-center position.

Optional stick mounted camera allows the operator to see in even the most difficult spaces.

APPLICATIONS

- Pipe Handling
- Drill Rod Handling
- Vertical Handling of Pilings and Poles
- I-Beam Placement



MAXIMUM TILT AND SHIFT

25° // 5.5"

LIFTING CAPACITY

10,000 LBS

4,536 KGS

UNIT WEIGHT

1,749 LBS

793 KGS

